

## Appendix 1 - Schedule of Quantities and Prices

Updated on June 1, 2026

	Item	Quantity	Units	Unit Rate	Total Cost
				(\$)	(\$)
<b>General Contract Considerations</b>					
1.1	Mobilization and Demobilization	1	LS		
1.2	Site Survey (including RFIS, Measurements, Submittals, Record Drawings)	1	LS		
<b>Sub-Total</b>					
<b>Site Grading</b>					
2.1	Clearing, Grubbing, and Stripping (Berm Footprint, Quarry Area, Access Road Alignment and Existing berm / new fill interface )	13,800	m2		
2.2	Excavate, Relocate, and Stockpile Existing Till Layer (Approx. 1.0 m Thick) from Berm Footprint, Quarry Area, and Existing Berm / New Fill Interface	13,800	m2		
2.3	Relocate Waste Rock and Construct Berm in Maximum 300 mm Thick Lifts, Including Minimum Four Roller Passes per Lift	16,800	m3		
2.4	Place and Compact Salvaged Till as a 1.0 m Thick Layer on Berm and Quarry Area	15,600	m2		
2.5	Supply and Place New Till	2,300	m3		
2.6	Shape 1.0 m Deep V-Ditch Along Both Sides of West Segment of New Access Road	500	m		
2.7	Grade and Compact Existing Till Surface to Form New Access Road Subgrade Suitable for Vehicle Access	1,000	m2		
<b>Sub-Total</b>					
<b>Erosion Control</b>					
3.1	Supply and apply Hydroseed Quarry Area and Outer 2.5H:1V Slope of New Berm	5,500	m <sup>2</sup>		
<b>Sub-Total</b>					
<b>Optional Work</b>					
4.1	Supply and Install 8 oz. Non-woven Geotextile	1,000	m2		
4.2	Supply, Place, and Compact 150 mm Thick Layer of Non-PAG 25–75 mm Crush	1,000	m2		
4.3	Supply, Place, and Compact 100 mm Thick Layer of Non-PAG Minus 19 mm Crush	1,000	m2		
4.4	Supply and Install No-Post Barriers on Outer Shoulder	130	m		
4.5	Supply and Install 450 mm Diameter Double-Wall Corrugated HDPE Culvert Pipe to Connect Roadside Ditches	15	m		
<b>Sub-Total</b>					
<b>Sub-Total (Excluding GST)</b>					
<b>GST (5%)</b>					
<b>Total (Including GST)</b>					



Gibraltar Landfill Phase 3C (2026-2027)

(TITLE OF CONTRACT)

See paragraph 5.3.3 of the Instructions to Tenderers – Part II.

**Name:** \_\_\_\_\_

**Experience:** \_\_\_\_\_

**Dates:** \_\_\_\_\_

Project Name: \_\_\_\_\_

Responsibility: \_\_\_\_\_

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

References: \_\_\_\_\_

\_\_\_\_\_

**Dates:** \_\_\_\_\_

Project Name: \_\_\_\_\_

Responsibility: \_\_\_\_\_

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

References: \_\_\_\_\_

\_\_\_\_\_

**Dates:** \_\_\_\_\_

Project Name: \_\_\_\_\_

Responsibility: \_\_\_\_\_

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

References: \_\_\_\_\_

\_\_\_\_\_

**Dates:** \_\_\_\_\_

Project Name: \_\_\_\_\_

Responsibility: \_\_\_\_\_

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

References: \_\_\_\_\_

\_\_\_\_\_

Tenderer's Initials \_\_\_\_\_



