



EMERGENCY RESPONSE PLAN

ALEXIS CREEK SEWER SYSTEM

INTRODUCTION

An ERP is a written document that spells out a sewer system's plan of action for responding to potential emergencies, disasters or abnormal operational circumstances. This plan is to provide guidelines that will minimize disruption of normal customer services and protect public health and safety if an incident should occur.

Each ERP must include the following information:

- a) the names and telephone numbers of
 - i) the management personnel for the sewer system,
 - ii) Medical Health Officer and Public Health Inspector, and
 - ii) other agencies and officials;
- b) the persons referred to in paragraph (a) to be contacted in each type of emergency or abnormal operational circumstance;
- c) the steps to follow in the event of an emergency or abnormal operational circumstances;
- d) protocols to follow respecting public notice if an immediate reporting standard cannot be met.

This specific ERP was developed by the Cariboo Regional District for the Alexis Creek Sewer System. Within this plan, specific community and CRD staff members are identified and assigned guideline procedures and appointed responsibilities. In the case of an incident, it is vital that these identified individuals be familiar with the scope of the ERP and their appointed responsibilities. This is to insure that if an incident should occur, the safety of the public served by this sewer system is guaranteed and service disruption is minimal.



EMERGENCY RESPONSE PLAN

ALEXIS CREEK SEWER SYTEM

TABLE OF CONTENTS - EMERGENCY RESPONSE PLAN – ACTION LIST

Type of Emergency: Contamination – Manhole Overflow	1
Type of Emergency: Sewage Discharge to Land	1
Type of Emergency: Sewage Discharge to Water (Surface or Ground)	2
Type of Emergency: Berm Failure on Lagoon	2
Type of Emergency: Broken Gravity Main	2
Contact List: REMOVED AS PER <i>FREEDOM OF INFORMATION AND PROTECTION OF PRIVACY ACT</i>	



EMERGENCY RESPONSE PLAN

EMERGENCY RESPONSE PLAN * ACTION LIST

TYPE OF EMERGENCY: MANHOLE OVERFLOW

- ACTIONS:**
- Receive report of overflowing manhole
 - Obtain approximate location of manhole from the caller
 - Contact operator / contractor / supervisor
 - Contact septic tank hauler immediately and dispatch to location to pump and haul effluent to the treatment plant and remove blockage from collection main
 - If a sewage discharge to the environment has occurred, follow SEWAGE DISCHARGE procedures for land and or water as required
-

TYPE OF EMERGENCY: SEWAGE DISCHARGE TO LAND

- ACTIONS:**
- Contact operator / contractor / supervisor
 - Determine where sewage is flowing and advise EMBC
 - In coordination with EMBC and Communications, develop an appropriate public message and advise the public via radio or door to door flyer as most suited to the circumstances
 - Mark off infected area with tape and or temporary fencing and post warning signs
 - If possible, contain spilled sewage and remove utilizing septic tank hauler equipment
 - Obtain bagged lime and apply to ground infected areas for a minimum of three days
 - After three days, remove excess lime, fencing and warning signs
 - In consultation with EMBC, advise public when health / environmental threat is over
-



EMERGENCY RESPONSE PLAN

EMERGENCY RESPONSE PLAN * ACTION LIST

TYPE OF EMERGENCY: SEWAGE DISCHARGE TO WATER (SURFACE OR GROUND)

- ACTIONS:**
- Contact operation / contractor / supervisor
 - Determine where sewage is flowing (surface water and or groundwater well) and advise EMBC
 - In coordination with EMBC, develop an appropriate public message and advise the public via radio or door to door flyer as most suited to the circumstances
 - If possible, contain spill sewage to prevent further discharging to water and remove utilizing septic tank hauler equipment
 - Sample and monitor the water as directed by EMBC
 - For associated land discharge point follow SEWAGE DISCHARGE TO LAND procedures
 - In consultation with EMBC, advise public when environmental threat is over
-

TYPE OF EMERGENCY: BERM FAILURE ON LAGOON

- ACTIONS:**
- Contact operator / contractor / supervisor
 - If failure is on the outside perimeter of the aeration cell, lower the level to below the berm breach by pumping into the standby exfiltration cells. Follow SEWAGE DISCHARGE procedures for the land and or water as the circumstances require
 - If failure is on outside perimeter of one of the exfiltration cells, lower the level to below the berm breach by pumping into the standby exfiltration cell. Follow SEWAGE DISCHARGE procedures for land and or water as the circumstances require
 - Contact engineer to assess the problem and make repairs
-

TYPE OF EMERGENCY: BROKEN GRAVITY MAIN

- ACTIONS:**
- Obtain approximate location of break
 - Contact operator / contractor / supervisor
 - Arrange for pump and hauling of sewage to aeration cells
 - Follow SEWAGE DISCHARGE procedures for land and or water as the circumstances require
 - Undertake the appropriate repairs